



2" x 4" STAKE FROM INVERT TO 2' ABOVE EXISTING GRADE. STAKE SHALL BE CONTINUOUS AND REMAIN VERTICAL AFTER BACKFILLING. END SHALL BE PAINTED WHITE. SEE NOTE 2.

STAMP "S" 3" HIGH, 2" WIDE AND 1/2" DEEP ON TOP OF CURB AND GUTTER

APPROX. 17"

24" X 22" X 4" POURED-IN-PLACE 4000 PSI CONCRETE PAD, WHEN NOT INTEGRATED INTO CONCRETE SIDEWALK. SEE NOTE 3.

BACK OF WALK

22"

6"

PROPERTY LINE

PROPERTY LINE

- NOTES:**
1. SERVICE SHALL NOT BE BACKFILLED PRIOR TO INSPECTION.
  2. GREEN MAGNETIC TAPE WITH "CAUTION SEWER LINE BURIED BELOW" IN RED OR BLACK LETTERS SHALL BE LAID 1' ABOVE THE TOP OF THE SERVICE CONNECTION AND WRAPPED AROUND THE PLUG AT THE END OF THE SEWER LATERAL AND BROUGHT TO THE SURFACE WRAPPED AROUND THE 2" X 4" MARKER.
  3. IF THE SIDEWALK WILL BE INSTALLED DURING HOME CONSTRUCTION, INSTALL THE PIPE RISER 2" ABOVE GRADE AND DO NOT INSTALL A CONCRETE PAD.
  4. WHEN WASTEWATER MAINS ARE INSTALLED IN ALLEYS, CLEANOUTS ARE NOT REQUIRED.

**SERVICE CONNECTION WITH RISER**

**SERVICE CONNECTION WITHOUT RISER**

DRAWN	KRB
REV. DATE	MARCH 2026
APPR.	
DETAIL NO.	307